

Pre-Commencement Site Check

Thank you for choosing Centaur for your flooring product needs. Listed below are some general industry guidelines in preparing for the installation of your floor system:

- *The floor must be clean of all debris, plaster, dirt, etc.*
- *The rooms where installation is being done must be climate controlled.*
- *The subfloor must be leveled within 1/8" within a 10' radius using Portland Cement-based underlayment.*
- *The subfloor must be vacuumed.*
- *The slab must meet acceptable moisture range (8% or below).*
- *Permanent lighting must be installed and working.*
- *All other trades (i.e., HVAC, permanent lighting, electrical, painting, fire sprinklers and all ceiling work) needing access to the floor area we are installing must be completely finished.*
- *Adequate room must be available for storage and staging of materials.*
- *All non-gym flooring materials (gym equipment, fitness equipment, etc.) must be removed from the floor.*
- *The installer must be contacted prior to commencement about any specific time requirements (start and stop) that must be adhered to.*

While Centaur Floor Systems does not offer installation as part of our service, we do have recommended installers who are knowledgeable about installing our products and have acquired certifications where necessary:

WESTERN U.S.
KLWA, Inc.
Tom Armstrong
18520 Valencia St.
Hesperia, CA 92345
760-948-2912/ Cell: 760-401-0708

EASTERN U.S.
Centaur Eastern Installations
Karen Mayo/Doug Seeman
P.O. Box 10294
Southport, NC 28461
(910) 457-6481/Cell: 805-452-8774

Regardless of who you choose to complete your installation, please contact your installer regarding pre-commencement site preparation to ensure a smooth and timely installation of your new floor.